

## Panel Cubicles – K32

### Product Reference: Rearo Rapidfit Cubicles

**Manufacturer:** Rearo Laminates  
**Address:** 29 Loanbank Quadrant, Glasgow G51 3HZ  
**T:** 0141 440 0800  
**E:** [commercial@rearo.co.uk](mailto:commercial@rearo.co.uk)  
**Web:** [www.rearo.co.uk/commercial](http://www.rearo.co.uk/commercial)

#### Panels:

- Height (overall): Standard 1950mm FFL.
- Floor Clearance: 150mm.
- Depth: Standard 1500mm
- Core material: Moisture Resistant Melamine-Faced Chipboard (MR MFC).
- Thickness: 18mm.
- Colour: From the Rearo Rapidfit colour chart.
- Edge treatment: All edges square & lipped with 2mm PVC edging.
- Wall Support: Satin anodised aluminium U – Channel brackets with Anti Vandal fixings

#### Pilasters:

- Panel Height: 1800mm.
- Core material: Moisture Resistant Melamine-Faced Chipboard (MR MFC).
- Thickness: 18mm.
- Colour: From the Rearo Rapidfit colour chart.
- Edge treatment: All edges square & lipped with 2mm PVC edging.
- Ironmongery: Satin anodised aluminium U – Channel brackets with Anti Vandal fixings

#### Doors:

- Panel Height: 1800mm.
- Core material: Moisture Resistant Melamine-Faced Chipboard (MR MFC) Pre-drilled to suit Hinge and Indicator bolt positions.
- Thickness: 18mm.
- Colour: From the Rearo Rapidfit colour chart.
- Edge treatment: All edges square & lipped with 2mm PVC edging.
- Ironmongery: Indicator Bolt - Coin operated emergency release including keeper with concealed fixings.  
Hinges - Satin anodised aluminium butt hinges with nylon cams to set closed door position. Coat Hook: Satin anodised aluminium coat hook with buffer.

#### Fittings:

- Headrail: Satin anodised aluminium.
- Legs: 150mm high satin anodised aluminium adjustable legs.

#### Accessories:

- Headrail End Caps: Satin anodised aluminium, to suit corner sited / free standing cubicles.
- Outward Opening Keeper: Satin anodised aluminium, to suit outward opening doors.

### INSTALLATION

- *Programming: Do not install cubicles or duct/ wall panels before building is weathertight, wet trades have finished their work, wall and floor finishes are complete, and the building is well dried out.*
- *Accuracy: Set out to ensure frames and/ or panels and doors are plumb, level and accurately aligned.*
- *Modifications: Do not cut, plane or sand prefinished components except where shown on drawings.*
- *Fixing: Secure components using methods and fasteners recommended by the cubicle/ panel manufacturer. Prevent pulling away, bowing or other distortions to frames, panels and doors.*
- *Moisture and thermal movement: Make adequate allowance for future movement.*